# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT19297/CALL-2

## APPROVED SCHEDULE - B

**EE/ETP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016**

**Construction of Culverts and Providing Covering Slab to Existing Drains and Kerb Stone at Navodaya School Road in ward no 11 (Kuvempunagara) Vidyaranyapura Sub Division**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of K Gopi Reddy | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 1 | 155.25 | Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work | Cum | 80.0 | 12420.00 | Rupees Eighty Only |
| 2 | 243 | Removing B.S Slab of Drain and stacking etc complete as per specifications and directions of engineer in charge of the work | Sqm | 60.0 | 14580.00 | Rupees Sixty Only |
| 3 | 243 | Refixing stone slabs of drains and pointing in C.M (1:3) etc complete as per specifications and directions of engineer in charge of the work | Sqm | 70.0 | 17010.00 | Rupees Seventy Only |
| 4 | 10.8 | Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work | Cum | 5000.02 | 54000.22 | Rupees Five Thousand and Two Paise Only |
| 5 | 38.88 | Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work | Cum | 4700.0 | 182736.00 | Rupees Four Thousand Seven Hundred Only |
| 6 | 64.8 | Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work | Sqm | 90.0 | 5832.00 | Rupees Ninety Only |
| 7 | 30.88 | Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work | Cum | 5400.0 | 166752.00 | Rupees Five Thousand Four Hundred Only |
| 8 | 408 | Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work | Sqm | 1000.0 | 408000.00 | Rupees One Thousand Only |
| 9 | 43.13 | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work | Sqm | 300.0 | 12939.00 | Rupees Three Hundred Only |

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of K Gopi Reddy | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 10 | 14.9 | Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams etc complete as per specifications and directions of engineer in charge of the work | Cum | 6200.0 | 92380.00 | Rupees Six Thousand Two Hundred Only |
| 11 | 1.49 | Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work | Tonne | 69000.0 | 102810.00 | Rupees Sixty Nine Thousand Only |
| 12 | 306 | Providing and laying precast drain cover slab of 100 mm thickness in CM 1.3 including cost of all materials, labours, curing, transportation, loading and unloading etc complete as per the direction of engineer in charge of work (RA as per BBMP) | Sqm | 2000.0 | 612000.00 | Rupees Two Thousand Only |
| 13 | 756 | Providing and fixing pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with top and bottom width 114 and 165mm repectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including, cost of all materials, labour hire charges of machinery, loading unloading, lead and lift, transportation etc complete as per specifications and directions of engineer in charge of the work | Nos | 304.0 | 229824.00 | Rupees Three Hundred Four Only |
| 14 | 136 | Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after throughtly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work | Sqm | 20.0 | 2720.00 | Rupees Twenty Only |
| 15 | 136 | Providing and applying floor painting with ready mix two coats (Excluding priming coat) on new s concrete / masonry / asbestos cement sheet / / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work | Sqm | 51.37 | 6986.32 | Rupees Fifty One and Thirty Seven Paise Only |
| 16 | 155.25 | Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 11.90 Km etc complete as per specifications and directions of engineer in charge of the work | Cum | 100.0 | 15525.00 | Rupees One Hundred Only |
| | | | | | 1936514.54 | |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

5/5/16